


We have presented the Graphical Abstract text and image for your article below. This brief summary of your work will appear in the contents pages of the issue in which your article appears.



### Na-promoted Ni/ZrO<sub>2</sub> dry reforming catalyst with high efficiency: details of Na<sub>2</sub>O–ZrO<sub>2</sub>–Ni interaction controlling activity and coke formation

M. Németh, D. Srankó, J. Károlyi, F. Somodi, Z. Schay, G. Sáfrán, I. Sajó and A. Horváth\*

Balanced, strong interaction of Ni–Na<sub>2</sub>O–ZrO<sub>2</sub> catalyst components under CO<sub>2</sub> reforming of methane is a criterion of good catalytic activity and stability.

Please check this proof carefully. **Our staff will not read it in detail after you have returned it.**

**Proof corrections must be returned as a single set of corrections, approved by all co-authors.** No further corrections can be made after you have submitted your proof corrections as we will publish your article online as soon as possible after they are received.

Please ensure that:

- The spelling and format of all author names and affiliations are checked carefully. Names will be indexed and cited as shown on the proof, so these must be correct.
- Any funding bodies have been acknowledged appropriately.
- All of the editor's queries are answered.
- Any necessary attachments, such as updated images or ESI files, are provided.

Translation errors between word-processor files and typesetting systems can occur so the whole proof needs to be read. Please pay particular attention to: tables; equations; numerical data; figures and graphics; and references.

Please send your corrections preferably as a copy of the proof PDF with electronic notes attached or alternatively as a list of corrections – do not change the text within the PDF file or send a revised manuscript. Corrections at this stage should be minor and not involve extensive changes.

Please return your **final** corrections, where possible within **48 hours** of receipt, by e-mail to: [catalysis@rsc.org](mailto:catalysis@rsc.org). If you require more time, please notify us by email.

## Funder information

Providing accurate funding information will enable us to help you comply with your funders' reporting mandates. Clear acknowledgement of funder support is an important consideration in funding evaluation and can increase your chances of securing funding in the future. We work closely with Crossref to make your research discoverable through the Funding Data search tool (<http://search.crossref.org/fundref>).

Further information on how to acknowledge your funders can be found on our webpage (<http://rsc.li/funding-info>).

### What is Funding Data?

Funding Data (<http://www.crossref.org/fundingdata/>) provides a reliable way to track the impact of the work that funders support. We collect funding information from our authors and match this information to funders listed in the Open Funder Registry. Once an article has been matched to its funders, it is discoverable through Crossref's search interface.

### PubMed Central

Accurate funder information will also help us identify articles that are mandated to be deposited in PubMed Central (PMC) and deposit these on your behalf.

## Providing funder information

We have included the funder information you gave us on submission in the table below. The 'Funder name' shown and their associated 'Funder ID' number is written as listed in the Open Funder Registry. **Please check that the funder names and grant numbers in the table are correct.** The funder information should match your acknowledgements. This table will not be included in your final PDF but we will share the data with Crossref so that your article can be found *via* the Funding Data search tool.

Funder name	Funder ID (from the Open Funder Registry)	Award/grant/contract number
-------------	---	-----------------------------

If a funding organisation you included on submission of your article is not currently listed in the registry it will not appear in the table above. We can only deposit data if funders are already listed in the Open Funder Registry, but we will pass all funding information on to Crossref so that additional funders can be included in future.

## Researcher information

If any authors have ORCID or ResearcherID details that are not listed below, please provide these with your proof corrections.

Please check that the ORCID and ResearcherID details listed below have been assigned to the correct author. Please use this space to add your own unique ORCID iDs and not another researcher's, as errors will delay publication.

Please also update your account on our online manuscript submission system to add your ORCID details, which will then be automatically included in all future submissions. See [here](#) for step-by-step instructions and more information on author identifiers.

First (given) name(s)	Last (family) name(s)	ResearcherID	ORCID
M.	Németh		
D.	Srankó		
J.	Károlyi		
F.	Somodi		

Z.	Schay		
G.	Sáfrán		
I.	Sajó		
A.	Horváth		0000-0002-5962-0015

## Queries for the attention of the authors

Journal: Catalysis Science & Technology

Paper: c7cy01011g

Title: Na-promoted Ni/ZrO<sub>2</sub> dry reforming catalyst with high efficiency: details of Na<sub>2</sub>O–ZrO<sub>2</sub>–Ni interaction controlling activity and coke formation

For your information: You can cite this article before you receive notification of the page numbers by using the following format: (authors), Catal. Sci. Technol., (year), DOI: 10.1039/c7cy01011g.

Editor's queries are marked on your proof like this **Q1**, **Q2**, etc. and for your convenience line numbers are indicated like this 5, 10, 15, ...

Please ensure that all queries are answered when returning your proof corrections so that publication of your article is not delayed.

Query Reference	Query	Remarks
Q1	Please carefully check the spelling of all author names. This is important for the correct indexing and future citation of your article. No late corrections can be made.	
Q2	The sentence beginning "The location of..." has been altered for clarity, please check that the meaning is correct.	
Q3	The sentence beginning "The differences between..." has been altered for clarity, please check that the meaning is correct.	
Q4	Please check that the term " $L h^{-1} g_{cat}^{-1}$ " has been presented correctly throughout the manuscript.	
Q5	The sentence beginning "TPR experiments revealed..." has been altered for clarity, please check that the meaning is correct.	
Q6	In the sentence beginning "In the case..." should the citation to Fig. 6 be changed to Fig. S4?	
Q7	The sentence beginning "Some metallic Ni..." has been altered for clarity, please check that the meaning is correct.	
Q8	Please note that a conflict of interest statement is required for all manuscripts. Please read our policy on Conflicts of interest ( <a href="http://rsc.li/conflicts">http://rsc.li/conflicts</a> ) and provide a statement with your proof corrections. If no conflicts exist, please state that "There are no conflicts to declare".	
Q9	Ref. 25: Can this reference be updated? If so, please provide the relevant information such as year, volume and page or article numbers as appropriate.	

## Na-promoted Ni/ZrO<sub>2</sub> dry reforming catalyst with high efficiency: details of Na<sub>2</sub>O–ZrO<sub>2</sub>–Ni interaction controlling activity and coke formation†

Cite this: DOI: 10.1039/c7cy01011g

Q1

M. Németh,<sup>a</sup> D. Srankó,<sup>a</sup> J. Károlyi,<sup>a</sup> F. Somodi,<sup>a</sup> Z. Schay,<sup>a</sup> G. Sáfrán,<sup>b</sup> I. Sajó<sup>c</sup> and A. Horváth<sup>id</sup>\*<sup>a</sup>

Herein, a 0.6 wt% Na-promoted 3% Ni/ZrO<sub>2</sub> dry reforming catalyst and its unpromoted counterpart are discussed in detail. Structural investigations were carried out using TEM, TPR, XRD, XPS, and CO pulse chemisorption followed by TPD and DRIFTS methods. In the presence of a dry reforming mixture, bidentate carbonates were detected on Na-promoted Ni/ZrO<sub>2</sub>, while on Ni/ZrO<sub>2</sub> effective hydrogenation by metallic Ni converted bicarbonates to formate species. In continuous flow atmospheric catalytic tests in a high excess of methane, a reactive-type coke was formed on the promoted sample, which did not cause significant deactivation. Temperature ramped <sup>13</sup>C<sub>2</sub>O<sub>2</sub> isotope labeled dry reforming experiments in a closed loop sub-atmospheric circulation system revealed <sup>13</sup>CH<sub>4</sub> formation on Ni/ZrO<sub>2</sub>, while in the case of the promoted catalyst methanation was retarded until the complete consumption of oxidants (from <sup>13</sup>CO<sub>2</sub>). In isothermal experiments in the same circulation system carbon monoxide disproportionation was observed on Ni/ZrO<sub>2</sub> leaving carbon on Ni, besides the coke formed from the CH<sub>4</sub> source, while on the promoted catalyst carbonaceous deposit under the same conditions did not form from CH<sub>4</sub>. The superb catalytic properties of Na-promoted Ni/ZrO<sub>2</sub> are explained by a proposed catalytic cycle compiling the dynamic participation (formation and decomposition) of the surface Na<sub>2</sub>CO<sub>3</sub> or NaHCO<sub>3</sub> species surrounding the NiO<sub>x</sub>H<sub>y</sub> active sites on a ZrO<sub>2</sub> support that is able to accommodate the labile Na<sub>2</sub>O promoter capturing and releasing CO<sub>2</sub> oxidant.

Received 18th May 2017,  
Accepted 5th August 2017

DOI: 10.1039/c7cy01011g


rsc.li/catalysis

### Introduction

Carbon dioxide reforming or dry reforming of methane (DRM) is a target reaction of high importance in CO<sub>2</sub>-rich natural gas or biogas conversion. Although a few pilot plants have already been working worldwide under dry reforming or – combined with steam – bi-reforming conditions,<sup>1</sup> there is still much to improve or even understand at the level of basic research. The strongly endothermic dry reforming reaction (1)



yields syngas with an equimolar ratio of carbon monoxide and hydrogen. Depending on the reaction parameters, several side reactions may simultaneously proceed, influencing the final H<sub>2</sub>/CO ratio. Among them, the water-gas shift reaction (WGSR) (2) is usually considered the most responsible for the H<sub>2</sub>/CO ≠ 1 ratio because it may proceed in a forward or backward direction within the overall temperature interval of dry reforming<sup>2</sup>



Concerning the reaction mechanism, the general view is that methane dissociates on the metal surface,<sup>3,4</sup> and CO<sub>2</sub> is activated on the support,<sup>5,6</sup> at the metal–support interface<sup>7,8</sup> or even on the metal surface,<sup>6,9</sup> depending on the reaction conditions and type of support and active metal.<sup>10,11</sup> In the next step, the surface CH<sub>x</sub> fragments (x = 0–3) react with active O or OH species and form a CH<sub>x</sub>O<sub>s</sub> like intermediate that after decomposition produces CO and H<sub>2</sub> products.<sup>12–14</sup> The suggested rate-determining steps vary with the catalyst system and reaction conditions.<sup>15</sup>

<sup>a</sup> Institute for Energy Security and Environmental Safety, Centre for Energy Research, Konkoly-Thege M. street 29-33, H-1121 Budapest, Hungary.  
E-mail: horvath.anita@energia.mta.hu

<sup>b</sup> Institute for Technical Physics and Materials Science, Centre for Energy Research, Konkoly-Thege M. street 29-33, H-1121 Budapest, Hungary

<sup>c</sup> Szentágotthai Research Centre, University of Pécs, Ifjúság street 20, H-7624 Pécs, Hungary

† Electronic supplementary information (ESI) available. See DOI: 10.1039/c7cy01011g

1 The hardest problem is tackling with the coke formation  
under the harsh, oxygen lean reaction conditions (low CO<sub>2</sub> or  
water concentration) that usually cause fast deactivation of  
5 Ni-based catalysts.<sup>16–18</sup> Coke deposition takes place and  
nanotubes or encapsulating graphitic layers form if the rate  
of surface carbon formation surpasses its gasification rate.  
Surprisingly, significant coke deposits can still let the catalyst  
10 work.<sup>19–22</sup> This is why the amount of deposited coke cannot  
be simply correlated with the catalytic performance and actu-  
ally there is no straightforward relationship between the  
quantity of carbon deposition and the activity. The location  
of carbon can be quite different: according to the simplest  
15 picture, if carbon covers the metal surface, the activity de-  
creases, but if the carbon transfers to the support surface or  
is produced at the metal–support interface, the dry reforming  
Q2 reaction may proceed further. According to Efstathiou and  
his co-workers,<sup>23</sup> we can distinguish between active and in-  
active carbon. Inactive carbon deposits are produced *via* poly-  
merization of surface carbon species to graphite layers and  
20 carbon whiskers. The active surface carbon (C<sub>s</sub>) can react  
with oxygen containing surface species (O<sub>s</sub> or OH<sub>s</sub>) and form  
CO desorbing into the gas phase. We should point out that  
only steady state transient kinetic analysis (SSITKA) is able to  
measure the usually very low surface coverage of active car-  
25 bon that truly participates in the formation of CO by using la-  
beled carbon dioxide or methane. As for the inactive surface  
carbon, Efstathiou *et al.*<sup>24,25</sup> determined the relative contribu-  
tion of a CO<sub>2</sub> activation route towards its formation *via* apply-  
ing a labeled reactant under strictly controlled conditions.  
The share of the CO<sub>2</sub> or CH<sub>4</sub> activation route in yielding car-  
30 bon deposit depended strongly on the reaction temperature  
and the chemical composition of the support for Ni  
supported on reducible Pr–Zr oxides or Ce–Zr oxides.<sup>23–25</sup>

35 Reducible supports such as CeO<sub>2</sub> with high oxygen mobil-  
ity,<sup>19</sup> basic supports enhancing the CO<sub>2</sub> adsorption/activation  
step<sup>4,10,26,27</sup> or addition of alkaline (K, CaO) promoters to the  
support<sup>5,6,28,29</sup> may help to diminish coke formation, because  
carbonates formed by CO<sub>2</sub> adsorption at the metal–support  
perimeter sites are considered as scavengers of carbon.<sup>6</sup>

40 Among alkali promoters, the effect of potassium or sodium  
promotion was studied mostly in the methanation reaction, and  
dry reforming studies in this respect are less in number. The  
overall view of these investigations was that the alkali/sodium  
promoter decreases the amount of deposited coke; however, the  
45 concentration of promoter and the synthesis method can greatly  
influence the catalytic properties. CO hydrogenation was studied  
on co-precipitated Na–Mn–Ni catalyst and compared to the refer-  
ence Ni/SiO<sub>2</sub>, a good methanation catalyst: here, Na was found  
to decrease the methanation activity and also the CO dissocia-  
50 tion.<sup>30</sup> Potassium-modified Ru/SiO<sub>2</sub> was tested for methanation  
and Fischer–Tropsch synthesis, and again, selective poisoning of  
methanation and more strongly bound bridged CO were ob-  
served.<sup>31</sup> Catalytic oxidation of formaldehyde at room tempera-  
ture was studied on 1% Pd/TiO<sub>2</sub> promoted by 2% Na by co-im-  
55 pregnation, and a negatively charged Pd surface was detected by  
XPS supposedly due to electron donation by sodium.<sup>32</sup>

As for dry reforming specifically, Lovell and his co-  
1 workers<sup>20</sup> pointed out that the Na content of Ni/MCM caused  
lower DRM activity and higher RWGS contribution. In this  
case the Na-modified support was first prepared and then im-  
pregnated with the Ni precursor in a second step. Higher sta-  
5 bility was observed by Ballarini and his co-workers<sup>28,29</sup> upon  
Na addition to Pt/ZrO<sub>2</sub> and Pt/Al<sub>2</sub>O<sub>3</sub> due to the creation of ba-  
sic sites, but a positive effect of the sodium species was ob-  
served on Pt/Al<sub>2</sub>O<sub>3</sub> only above 0.5 wt% Pt content. In this case  
Na or K was added again to the support followed by calcina-  
10 tion and impregnation with the Pt salt.

A deeper and more adequate investigation of the effect  
of alkali promotion of 10% Ni/Al<sub>2</sub>O<sub>3</sub> was published by  
Mori *et al.*<sup>33,34</sup> They declared that oxides of Na, K, Mg,  
and Ca markedly suppress carbon deposition during CO<sub>2</sub>  
15 reforming *via* the decrease of the CH<sub>4</sub> decomposition abil-  
ity of nickel (note that alkaline promoters were post im-  
pregnated onto the calcined nickel catalyst). Based on the  
determined reaction orders of CH<sub>4</sub> and CO<sub>2</sub>, it was de-  
clared that the surface of a 10% CaO-modified Ni/Al<sub>2</sub>O<sub>3</sub>  
20 catalyst was supposed to be abundant in adsorbed CO<sub>2</sub> in-  
stead of methane. The kinetics of the individual steps of  
reforming were further examined<sup>34</sup> on Ni/Al<sub>2</sub>O<sub>3</sub> loaded  
with 0–10 wt% K. Although the adsorption of CO<sub>2</sub> was en-  
hanced by the presence of potassium, the dissociation of  
25 CO<sub>2</sub> to CO and O<sub>s</sub> was not significantly influenced. This  
suggested that the enhancement of the oxidation of CH<sub>x</sub>  
by increasing the concentration of O<sub>s</sub> is not the cause of  
the carbon-free CO<sub>2</sub> reforming but the physical blockade  
of Ni ensemble by potassium.  
30

Until now, different supported metal catalysts for dry  
reforming have been studied in our laboratory.<sup>19,26,27</sup>  
Sodium-promoted 1% Ni, 3% Ni and 1% Pt/ZrO<sub>2</sub> catalysts  
proved to be very effective in short range low temperature  
35 activity tests,<sup>35</sup> and this inspired us to conduct further re-  
search on how the Na<sub>2</sub>O promoter acts under different re-  
action conditions and longer time on stream compared to  
an unpromoted sample. In the present manuscript we will  
pay special attention to the Ni–Na<sub>2</sub>O–ZrO<sub>2</sub> interface that is  
40 thought to influence the catalytic properties, taking the  
highly active and stable 3% Ni/ZrO<sub>2</sub> catalyst promoted with  
0.6 wt% Na as an example. The differences between the  
promoted and the unpromoted sample before and after the  
catalytic runs are studied by X-ray powder diffraction  
45 (XRD), transmission electron microscopy (TEM), X-ray  
photoelectron spectroscopy (XPS) and diffuse reflectance in-  
frared spectroscopy (DRIFTS). The catalytic behavior is eval-  
uated in a fixed bed tubular reactor in high excess (70%)  
Q3 of methane and in a closed loop circulation system at sub-  
atmospheric pressure, using labeled <sup>13</sup>CO<sub>2</sub> reactant that al-  
50 lows us to follow the interconversion of carbon atoms of  
both reactants. Transmission electron microscopy and tem-  
perature programmed oxidation of deposited coke after the  
reactions can shed some light on the intimate interaction  
of Ni–Na<sub>2</sub>O–ZrO<sub>2</sub> components leading to an active and sta-  
55 ble catalyst.

# Experimental

## Sample preparation

Zr hydroxide from MEL Chemicals was calcined at 600 °C resulting in ZrO<sub>2</sub> with about 40 m<sup>2</sup> g<sup>-1</sup> surface area. The preparation of base 3% Ni/ZrO<sub>2</sub> was done by incipient wetness impregnation of ZrO<sub>2</sub> with Ni(NO<sub>3</sub>)<sub>2</sub> solution (denoted as Ni/ZrO<sub>2</sub> sample). The preparation of the Na<sub>2</sub>O-promoted 3% Ni/ZrO<sub>2</sub> catalyst (denoted as Na-Ni/ZrO<sub>2</sub>) is described in ref. 35. Briefly, the pH of the aqueous suspension of ZrO<sub>2</sub> powder and Ni nitrate precursor was set to pH 6.5 using NaHCO<sub>3</sub> (resulting in a final 0.6 wt% Na loading) and heated to 70 °C, then the water was slowly evaporated over 3–4 hours, and the solid was dried. A parent Na-promoted support was prepared in the same way without addition of Ni nitrate (denoted as Na-ZrO<sub>2</sub>). Dried samples were calcined in air at 600 °C, reduced in H<sub>2</sub> at 600 °C for 2 hours and stored in air before further use (these are referred to as as-received samples from here on).

## Catalyst characterization

The reduction properties of the oxidized catalyst samples were investigated in a Micromeritics AutoChem 2920 catalyst characterization system. TCD response was calibrated in a separate measurement before the temperature programmed reduction (TPR) run. 50 mg as-received catalysts were first oxidized at 700 °C for 1 h in a 10% O<sub>2</sub>/He stream, cooled under Ar and reduced in a 10% H<sub>2</sub>/Ar stream with a 10 °C min<sup>-1</sup> temperature ramp up to 700 °C followed by a 1 hour isothermal hold. Reducibility was calculated based on the H<sub>2</sub> consumption supposing that NiO was reduced during the TPR.

CO pulse chemisorption measurements were conducted with 10% CO/He pulses in a Micromeritics AutoChem 2920 flow system after the first TPR run. The Ni dispersion in % was calculated by determining the moles of CO molecules adsorbed from the pulses at standard temperature and pressure/moles of Ni in the sample, assuming CO:Ni = 1 chemisorption stoichiometry (this means each metallic surface Ni atom is able to bind a CO molecule that does not dissociate at the temperature of measurement and the chemisorption is strong and irreversible under the flow of the inert He gas). After the CO pulses, temperature programmed desorption (CO-TPD) experiments under He were carried out up to 700 °C and monitored using QMS analysis.

The phase composition of crystalline components was investigated by X-ray powder diffraction (XRPD) analyses after the above listed measurements (TPR and CO TPD). The diffraction patterns were obtained using a Phillips model PW 3710 based PW 1050 Bragg–Brentano para-focusing goniometer using CuK<sub>α</sub> radiation ( $\lambda = 0.15418$  nm) with a graphite monochromator and a proportional counter. The digitally recorded XRD scans were evaluated for quantitative phase composition using a full profile fit method with corrections for preferred orientation and microabsorption. This method let us estimate the Ni particle size even if the diffraction peaks of metal and oxide are overlapped.

The morphology and structure of the catalysts and the carbon contamination after dry reforming tests were studied by transmission electron microscopy using a PHILIPS CM 20 conventional 200 kV TEM and a high resolution JEOL 3010 microscope operating at 300 kV with point resolution of 0.17 nm (HRTEM). The samples were prepared by drop drying the aqueous suspensions on carbon-coated micro grids.

For the determination of surface composition, X-ray photoelectron spectroscopy measurements were applied using a KRATOS XSAM 800 XPS machine equipped with an atmospheric reaction chamber. An Al K<sub>α</sub> characteristic X-ray line, 40 eV pass energy and FAT mode were applied for recording the XPS lines of Ni 2p, C 1s, O 1s, Zr 3d, and Na 1s. Adventitious carbon C 1s binding energy at 284.8 eV was used as reference for charge compensation. The samples were measured after *in situ* calcination in synthetic air at 600 °C for 30 min (10 °C min<sup>-1</sup>) and after the subsequent *in situ* H<sub>2</sub> treatment at 600 °C for 30 min (10 °C min<sup>-1</sup>) (an atmospheric pretreatment chamber connected to a UHV chamber with a load lock gate allows us to do pretreatments without allowing the sample to come in contact with air).

*In situ* diffuse reflectance infrared Fourier transform spectroscopy (DRIFTS) was applied to study the catalyst samples under different conditions. Spectra were collected on a Nicolet iS50 infrared spectrometer equipped with a MCT detector and a Specac DRIFT environmental chamber with a ZnSe window. The maximum allowed temperature of the cell was 500 °C. The introduced gas flow directly passed over the upper surface of the catalyst placed in the heatable sample holder of the DRIFTS cell facing the zinc selenide window. Spectra were obtained by collecting 64 scans with a resolution of 4 cm<sup>-1</sup> and presented as log(1/R) mode, where *R* is the reflectance. For *in situ* reduction, the sample in the DRIFTS cell was heated to 500 °C under a 5% H<sub>2</sub>/Ar atmosphere at a rate of 10 °C min<sup>-1</sup> and kept at this temperature for 30 min; then, it was cooled to the desired temperature of the measurement. CO chemisorption measurements at room temperature were done using 1% CO in He. Temperature programmed DRIFTS measurements were conducted in the presence of a CH<sub>4</sub>:CO<sub>2</sub> = 70:30 DRM reactant mixture (flow rate: 50 cc min<sup>-1</sup>) after the *in situ* reduction treatment. Spectra were taken from 300 °C to 500 °C.

## Catalytic measurements

**Catalytic and TPO measurements in a continuous flow fixed bed tubular reactor.** Two types of catalytic tests (short and stability tests) were done in the fixed bed reactor at 1 atm using a CH<sub>4</sub>:CO<sub>2</sub>:Ar = 68:31:1 mixture (from here on this is referred to as DRM mixture for the sake of simplicity). An extremely high concentration of methane was set to mimic biogas composition. 10 mg of catalyst along with 100 mg of diluting quartz beads were placed in the tubular quartz reactor where the reactant mixture was introduced at a flow rate of 20 mL min<sup>-1</sup> (120 L h<sup>-1</sup> g<sub>cat</sub><sup>-1</sup>). At the beginning of the short catalytic tests, the as-received samples were ramped at

10 °C min<sup>-1</sup> in a 30 mL min<sup>-1</sup> 90% H<sub>2</sub>/Ar stream to 600 °C and kept at this temperature for 30 min. After reduction, the sample was purged with He (30 mL min<sup>-1</sup>) while it cooled to room temperature. Next, the He flow was changed to the reactant gas mixture and the temperature was increased to 600 °C at 10 °C min<sup>-1</sup> followed by a 2 h hold time. The other type of catalytic experiments was the long-term isothermal stability test lasting for 24 hours. For these experiments, a new portion of the as-prepared sample was reduced with 90% H<sub>2</sub>/Ar by heating the catalyst to 750 °C at a rate of 10 °C min<sup>-1</sup> and maintaining this temperature for 30 min. Subsequently, the sample was cooled to 675 °C in 8 min while it was purged with He, then the flowing gas was switched to the DRM mixture. A quadrupole Pfeiffer Prisma mass spectrometer was connected *via* a differentially pumped quartz capillary to the reactor outlet. Due to the reaction stoichiometry that causes a volume flow increase at the outlet of the reactor, argon was used as an internal reference gas for calculation of the outlet mass flows to determine the H<sub>2</sub>/CO ratio and methane and carbon dioxide conversion values after adequate calibration.

The quantitative analysis was based on the following equation:

$$f_x \times \frac{I_x}{I_{Ar}} = \frac{F_x}{F_{Ar}}$$

where  $F_x$  = gas mass flow rate ( $x = \text{CH}_4, \text{CO}_2, \text{CO}$  or  $\text{H}_2$ ),  $F_{Ar}$  = mass flow rate of argon,  $I_{Ar}$  = mass signal of argon,  $I_x$  = mass signals ( $x = \text{CH}_4^+, \text{CO}_2^+, \text{CO}^+, \text{H}_2^+$ ), and  $f_x$  = calibration factor for each individual gas component.

The following mass signals as representatives of the gas components were measured: 2-H<sub>2</sub>, 15-CH<sub>4</sub>, 28-CO, and 44-CO<sub>2</sub>. In the quantification of mass signal  $m/z = 28$  (CO), the actual fragmentation of  $m/z = 44$  (CO<sub>2</sub>) was taken into account. The error in the carbon balance in the effluent was within ±5% in all measurements. The relative difference between two repeated catalytic runs was about 5%. Note that sampling was very fast and the linked symbols showing QMS signals in any of the figures are the results of skipping several measured points for the sake of clarity.

Temperature programmed oxidation (TPO) measurements were conducted in the same flow system to detect and measure carbon deposits formed in the DRM reaction. At the end of the short catalytic run, the gas flow was switched to He and the system was cooled to room temperature. Then, the samples were oxidized in a 30 mL min<sup>-1</sup> O<sub>2</sub>:He:Ar = 10:89:1 mixture by heating from ambient temperature to 600 °C at a rate of 10 °C min<sup>-1</sup> followed by a 30 min isothermal hold. After the stability test, the temperature during the TPO runs was increased to 750 °C. The CO<sub>2</sub> signal was used for quantification of coke after a calibration procedure.

**Catalytic and TPO measurements at sub-atmospheric pressure in a closed loop circulation system using <sup>13</sup>CO<sub>2</sub>.** An all-glass circulation system (shown in the ESI† in Fig. S1) was applied to conduct isotope-labeled reactions at sub-atmospheric pressure. In this setup a 1:1 ratio of the reactants, precisely 25

± 0.5 mbar CH<sub>4</sub> (containing 2% Ar) and 25 ± 0.5 mbar <sup>13</sup>CO<sub>2</sub> (99% purity, Consigour Ltd.), was applied. The system could be separated into the gas blending space and the reactor space, and these two could be merged when needed. Reactants were introduced by measuring the sequential pressure using a capacitive pressure gauge in the gas blending space. Circulation was carried out using a double-acting piston pump. During the experiments, the overall system containing a certain amount of gases ( $p = 50$  mbar for DRM and  $p = 200$  mbar for TPO) was monitored through a fine glass capillary connected to a Pfeiffer Prisma quadrupole mass spectrometer. DRM experiments in this circulation system are able to provide only qualitative results due to the nature of the capillary inlet system and the significant pressure increase during the reaction (MS calibration of all components would be elusive). The following mass signals were taken as representatives of the gas components: 2-H<sub>2</sub>, 15-CH<sub>4</sub>, 17-<sup>13</sup>CH<sub>4</sub>, 28-CO, 29-<sup>13</sup>CO, 40-Ar, 44-CO<sub>2</sub>, and 45-<sup>13</sup>CO<sub>2</sub>. It is also well known that H<sub>2</sub>O has a small contribution at  $m/z = 17$  and CO<sub>2</sub> molecules have a low intensity fragment signal at  $m/z = 28$  (or in the case of labeled <sup>13</sup>CO<sub>2</sub> at  $m/z = 29$ ). However, it was ascertained that the  $m/z = 17$  signal during dry reforming corresponded to the change of <sup>13</sup>CH<sub>4</sub> concentration and not to that of H<sub>2</sub>O. At the beginning of the experiments, 10 mg of the sample was placed into a U-shaped quartz reactor tube. After an *in situ* reduction treatment in H<sub>2</sub> flow at 600 °C for 30 min, the sample was cooled to 150 °C and evacuated to about  $1.5 \times 10^{-2}$  mbar pressure. There were 2 types of catalytic experiments ending with TPO measurements. In one case, the premixed reactants were introduced into the reduced, evacuated sample at about 150 °C; afterwards the temperature was ramped up to 600 °C at a 10 °C min<sup>-1</sup> rate and held there for 30 min, and then evacuated and cooled close to room temperature before the TPO measurements (ramp-hold type experiment). The other type of measurements was the isothermal runs at 600 °C, which means that the reduced sample in the reactor space was heated in vacuum to 600 °C; then the reactant mixture was introduced into the catalyst, and after 30 min it was evacuated and then cooled for the start of TPO. Terminal TPO measurements were carried out by adding 200 mbar oxygen to the evacuated catalyst and ramping the temperature again to 600 °C. The CO<sub>2</sub> signal (CO alone was not formed) detected at  $m/z = 44$  and  $m/z = 45$  was differentiated to get a peak-shaped curve instead of the original integral signal. In this case the CO<sub>2</sub> signal could be calibrated and the surface coke evolving as gas phase labeled or unlabeled carbon dioxide was quantified.

## Results and discussion

### Catalyst characterization

**Dispersion, TPR, XPS measurements and CO-TPD results.** Due to the nature of the preparation procedure (no possibility of metal loss), the Ni loadings were taken as the nominal values for both samples, *viz.* 3 wt% Ni. Based on the amount of NaHCO<sub>3</sub> added during the preparation, the sodium-promoted sample contains 0.6 wt% Na. The relatively long, mild heat treatment during preparation of Na-Ni/ZrO<sub>2</sub> was

done deliberately in the hope of getting some  $\text{Na}^+$  inclusion into the Ni phase to achieve localized promotion of Ni with a minute amount of Na and a uniform distribution of sodium on the  $\text{ZrO}_2$  surface. We suppose that during preparation, basic Ni carbonate was formed by polymerization of aquahydroxo complexes of  $\text{Ni}^{2+}$  according to ref. 36.

First, the temperature programmed reduction measurements will be discussed. A considerable difference was seen in the reduction behavior of the oxidized samples as depicted in Fig. 1. TPR experiments revealed 96.2% reducibility in the case of the Na-Ni/ $\text{ZrO}_2$  sample and 96.9% for the Ni/ $\text{ZrO}_2$  catalyst, supposing NiO to be the reducible compound. This means that a nearly complete reduction of the Ni oxide phase has already taken place below 600 °C in both samples. The NiO in weak interaction with the support was present in a considerable amount on Ni/ $\text{ZrO}_2$  and was reduced at around 315 °C. The  $\text{NiO}_x$  species in stronger interaction with the support<sup>37</sup> were reducible at 428 °C on this sample but only at 490 °C in the case of the sodium-containing counterpart. It seems that the Na incorporation resulted in a  $\text{NiO}_x$  phase that is relatively hard to reduce.

Determination of Ni size in the  $\text{ZrO}_2$  supported samples turned to be difficult using TEM due to the lack of sufficient contrast between the crystalline oxide support and the Ni particles. Metal particle size estimated by XRD could not provide firm results either, because the Ni (111) and the monoclinic baddeleyite  $\text{ZrO}_2$  peaks overlapped after calcination/reduction treatment at 600 °C.<sup>35</sup> XRD measurements were done on the samples after the TPR run as well, with the aim of detecting considerable sintering if any happened. The size of the Ni particles was estimated to be around 20 nm in both Ni samples (Table 1). No separate Ni peaks could be detected as seen in the XRD patterns in Fig. S2.† The only small difference is that a minute tetragonal  $\text{ZrO}_2$  phase originating from the support preparation process is still seen for the Ni/ $\text{ZrO}_2$  besides the prevailing monoclinic structure, while it is absent for Na-Ni/ $\text{ZrO}_2$ .

CO pulse chemisorption (see Table 1) after TPR revealed low Ni dispersion values for both samples. We must emphasize that these data were obtained by assuming a CO:Ni = 1




Fig. 1 Results of temperature programmed reduction on preoxidized Ni/ $\text{ZrO}_2$  and Na-Ni/ $\text{ZrO}_2$  samples.

Table 1 Results of dispersion measurements and the XPS surface concentrations in the reduced state

Sample name	Ni particle size by XRD <sup>a</sup>	Ni dispersion by CO pulse chemisorption <sup>a</sup>	XPS surface concentration <sup>b</sup>	
			Ni/Zr	Na/Zr
Na-Ni/ $\text{ZrO}_2$	20 nm	0.9%/114 nm	0.07	0.83
Ni/ $\text{ZrO}_2$	20 nm	2.2%/46 nm	0.04	0.08

<sup>a</sup> After TPR measurements. Particle size was calculated with CO:Ni = 1 stoichiometry supposing hemispherical shape. <sup>b</sup> After *in situ* calcination/reduction treatment at 600 °C.

chemisorption stoichiometry. However, the dispersion values are underestimated, because real CO bonding is not linear, but CO binds to more than 1 surface Ni atom in a bridged form (see FTIR data later). The other reason for the extremely low dispersion of Na-Ni/ $\text{ZrO}_2$  may be that sodium (oxide) suppresses the CO chemisorption if the Ni surface is partially covered after the high temperature reduction as was reported for Li, Na or K-doped Ni catalysts.<sup>34,38,39</sup> A similar conclusion was drawn in the case of Ni-CaO- $\text{ZrO}_2$  catalysts prepared by co-precipitation, when decoration of Ni by the support itself was thought to be the reason for the low dispersion measured by  $\text{H}_2$  chemisorption.<sup>37</sup>

Balakos and Chuang<sup>30</sup> also pointed out that changes during surface composition under reduction and reaction conditions give rise to uncertainty in  $\text{H}_2$  chemisorption based activity data. According to our results and the adequate literature, we might assume that a part of the Ni surface is electronically influenced or physically covered by  $\text{Na}_2\text{O}$  or  $\text{Na}_2\text{CO}_3$  patches during CO chemisorption on the promoted catalyst.

Table 1 summarizes the Ni and Na surface concentrations obtained by XPS investigation after *in situ* calcination/reduction treatment at 600 °C. Note that the  $\text{ZrO}_2$  support itself contains an insignificant amount of Na impurity, but the  $\text{NaHCO}_3$  addition during sample preparation causes a 10-fold increase in the Na/Zr ratio. If we consider that 0.6 wt% Na was added during preparation, the  $\text{Na/Zr}_{\text{bulk}}$  would be 0.03, but it is straightforward that Na is segregated and well dispersed on the surface because  $\text{Na/Zr}_{\text{surf}} = 0.83$  in the reduced state. A simple rough estimation supposing monolayer coverage of our  $\text{ZrO}_2$  with  $\text{Na}_2\text{O}$  reveals that a maximum of 20% of the  $\text{ZrO}_2$  surface might be covered ( $37 \text{ m}^2 \text{ g}^{-1}$  BET surface area of pure  $\text{ZrO}_2$  was used in the calculation). Thus, it should be accepted that sodium either exists as small  $\text{Na}_2\text{O}$  islands on the support or is integrated into the  $\text{ZrO}_2$  network forming diluted structures of  $\text{Na}_2\text{ZrO}_3$ . This possibility is really important since bulk  $\text{Na}_2\text{ZrO}_3$  was found to be a highly efficient high temperature ( $T > 500 \text{ °C}$ )  $\text{CO}_2$  absorbent that can bind and release  $\text{CO}_2$  depending on the temperature and partial pressure of the gas ( $\text{CO}_2 + \text{Na}_2\text{ZrO}_3 \rightleftharpoons \text{Na}_2\text{CO}_3 + \text{ZrO}_2$ ), according to ref. 40 and 41.

Investigating the C 1s region, the following statements could be drawn. The C 1s peak beside the main adventitious carbon component at 284.8 eV had a shoulder at 288.8 eV in the

calcined state of the promoted sample, corresponding to a carbonate type carbon (see Fig. S3†), while in the case of the unpromoted sample that shoulder was absent. It means that some carbonates are strongly held by the sodium dispersed on the  $ZrO_2$  support even after air treatment at 600 °C and evacuation. After *in situ* reduction, however, they are gone and only a little adventitious carbon remains on the surface (Fig. S3b†). The Na 1s peak after calcination and reduction was detected at 1071.9 eV (see Fig. S3c and d†). This  $Na_2O$  must be spread over the  $ZrO_2$  and connected to  $ZrO_2$  via Na–O–Zr entities. The small shoulder at an unusually low binding energy of 1068 eV (Fig. S3d†) in the promoted reduced sample supposedly belongs to sodium species in intimate contact with nickel.

Comparing the surface distribution of Ni obtained by XPS measurements (Ni/Zr in Table 1), the  $Na_2O$ -promoted sample seems to be more disperse based on the higher Ni/Zr ratio (in contrast to the CO pulse chemisorption data). Let us consider now the Ni states in both samples after *in situ* calcination treatment as shown in Fig. 2a and b (the fitted curves together with the measured ones are shown in Fig. S3†). The peak detected at 853.9 eV in the Ni 2p region can be assigned

to  $Ni^{2+}$  in the NiO phase in the case of the bare catalyst, while over the sodium-promoted sample the nickel signal could be fitted with 2 components, the one at 854.1 eV is  $Ni^{2+}$  present as NiO and the other component at 855.9 eV is assignable to Ni hydroxide. This  $Ni(OH)_2$  is supposedly responsible for the stronger oxide–support interaction as was observed during TPR measurements. The reduced Ni state seen in Fig. 2c and d significantly differs for the two samples. In the unpromoted catalyst, Ni is metallic (B.E. at 852.8 eV), but the sodium containing sample – besides metallic Ni – still has a significant contribution at 855.8 eV, corresponding to  $Ni^{2+}$  most probably in a  $NiO_xH_y$  species. This surface hydroxide-like nickel compound seems to be very stable even under a reducing atmosphere, although TPR suggested almost complete reduction of Ni oxide at 600 °C. This might be explained if we assume a well dispersed, thin layered form of Ni hydroxide. The other issue to note is the extremely low intensity satellite peak (Fig. 2d) compared to what one would expect based on the intensity of the apparent  $Ni(OH)_2$  ( $\sim NiO_xH_y$ ) component. This feature suggests that some unique electronic interaction prevails between nickel and




Fig. 2 Ni 2p region measured by XPS after calcination at 600 °C on (a) Ni/ $ZrO_2$  and (b) Na-Ni/ $ZrO_2$  and after reduction at 600 °C on (c) Ni/ $ZrO_2$  and (d) Na-Ni/ $ZrO_2$ . Fitted curves are shown.

other element(s) or even could be the sign of a mixed phase or alloy formation. We suppose that sodium ion is embedded in the  $\text{NiO}_x\text{H}_y\text{-Ni}$  matrix, resulting in decreased satellite intensity. This assumption is based on literature analogues. According to Roberts *et al.*,<sup>42</sup> the interaction of potassium with an oxidized Ni(110) single crystal during annealing resulted in the suppression of the NiO satellite structure due to the incorporation of alkali promoter into the oxide lattice. At 300 °C they observed  $\text{Ni}^{3+}$  species present probably as potassium nickelate ( $\text{K}_2\text{O}_2 + 2\text{NiO} = 2\text{KNiO}_2$ ). We cannot exclude or prove that some of the Ni is in the 3+ oxidation state after calcination due to the poor resolution and low signal intensity in Fig. 2b. However, under reducing atmosphere, the inclusion of some sodium oxide into the surface metallic/oxidized Ni compounds or just as a surface decoration is certainly reasonable based on these XPS results. We may even suggest that under a reducing atmosphere an interaction similar to the classic strong metal support interaction (SMSI) develops in the promoted catalyst and part of the metallic Ni surface is surrounded/buried by a Na-O-Zr network.

The different surface properties of the catalysts were studied by means of CO-TPD experiments carried out in He after CO pulse chemisorption and depicted in Fig. 3a-d. The

desorbing species were CO, CO<sub>2</sub> and H<sub>2</sub>O from both catalysts, while H<sub>2</sub> desorbed exclusively from the sodium promoted sample. The water desorption curve has a maximum at 150 °C followed by a broad tail and a distinct shoulder at 250 °C in the case of the sodium promoted sample (Fig. 3b), which means that molecular water or hydroxyl groups with a certain and quite uniform environment leave the surface at low temperature. Considering the presence of chemisorbed CO on Ni/NiO<sub>x</sub>H<sub>y</sub> and the hydroxyls of the support, a surface water-gas shift reaction may proceed, producing H<sub>2</sub> and CO<sub>2</sub> through a formate intermediate. The latter is decomposed to H<sub>2</sub> and CO<sub>2</sub> at low temperature<sup>43</sup> but the CO<sub>2</sub> re-adsorbs and desorbs together with the stable carbonates of the support at higher temperature only. The high temperature appearance of CO<sub>2</sub> with a peak maximum at 450 °C shows the much higher basicity of the sodium promoted sample as expected. The featureless H<sub>2</sub>O desorption curve with a maximum at around 300 °C for the unpromoted sample points to a wide distribution of strongly bound surface hydroxyls in this case. The absence of desorbing H<sub>2</sub> points to the inability of this catalyst to undergo the WGSR under the same conditions.

#### CO chemisorption and dry reforming followed by DRIFTS.

According to CO chemisorption in 1% CO/He flow on the




Fig. 3 Temperature programmed desorption spectrum in He flow after CO pulse chemisorption carried out on (a) Ni/ZrO<sub>2</sub> and (b) Na-Ni/ZrO<sub>2</sub> and the corresponding enlarged 28 (=CO) and 44 (=CO<sub>2</sub>) signals of (c) Ni/ZrO<sub>2</sub> and (d) Na-Ni/ZrO<sub>2</sub>. Note that the second peak in the  $m/z = 28$  signals corresponds only to the fragmentation of CO<sub>2</sub> in both cases.

reduced samples (see Fig. S4<sup>†</sup>), at room temperature linear CO on Ni metal<sup>44</sup> at  $2084\text{ cm}^{-1}$  with a shoulder at  $2052\text{ cm}^{-1}$  and bridging CO at  $1953\text{ cm}^{-1}$  form on the Ni/ZrO<sub>2</sub> sample (the band at  $1638\text{ cm}^{-1}$  is assigned to the bending mode of H<sub>2</sub>O). In the case of Na-Ni/ZrO<sub>2</sub>, the linear CO was seen at  $2061\text{ cm}^{-1}$  and there were two bands in the bridged CO region at  $1931\text{ cm}^{-1}$  and at  $1822\text{ cm}^{-1}$  (Fig. 6, curve B). Alkali promotion can cause a red shift in the stretching vibration wavenumbers of the corresponding carbonyl bonds.<sup>35,45,46</sup> Thus, we certainly assign the peak at around  $1820\text{ cm}^{-1}$  to CO adsorbed on Ni sites that are influenced by sodium or located in close vicinity of sodium, *viz.* at the metal-support interface. We may even suppose the existence of a tilted CO molecule with the oxygen end bonded to Na<sup>+</sup>.<sup>47</sup> We should emphasize that sodium promotion can change the typical IR frequency of a chemisorbed molecule *via* strengthening or weakening of a given bond that makes the band assignments more difficult. For example, Pigos *et al.*<sup>48</sup>

found that the formate bands were virtually indistinguishable from those of carbonates on a sodium-promoted Pt/ZrO<sub>2</sub> sample. Keeping this in mind, the bands at  $1572\text{ cm}^{-1}$ ,  $1475\text{ cm}^{-1}$  and  $1370\text{ cm}^{-1}$  are assigned to the presence of carbonate species<sup>49</sup> on the sodium-promoted sample.

In our previous contribution<sup>35</sup> we could not prove or exclude the role of carbonates in the coke oxidizing steps<sup>50</sup> because a suitable catalyst without sodium was not available. Our aim was now to follow the conversion of IR visible surface species during temperature increase up to  $500\text{ °C}$  in the presence of the DRM reaction mixture under very similar conditions to those of the forthcoming short catalytic tests (atmospheric pressure, CH<sub>4</sub>:CO<sub>2</sub> = 70:30 mixture,  $50\text{ cc min}^{-1}$  flow). Fig. 4 depicts DRIFTS spectra obtained on both samples and the corresponding supports in the presence of a DRM mixture during temperature ramp. The lowest ( $300\text{ °C}$ ) and the highest ( $500\text{ °C}$ ) spectra are compared. The gas phase CH<sub>4</sub> and CO<sub>2</sub> peaks can be easily





Fig. 4 DRIFTS spectra obtained in the presence of CH<sub>4</sub>:CO<sub>2</sub> = 70:30 DRM flow at (a)  $300\text{ °C}$  and (b)  $500\text{ °C}$ . Curve A: ZrO<sub>2</sub> support, B: Ni/ZrO<sub>2</sub>, C: Na-ZrO<sub>2</sub> support, D: Na-Ni/ZrO<sub>2</sub>.




**Fig. 5** Methane and CO<sub>2</sub> conversion curves and the H<sub>2</sub>/CO ratios during a short term catalytic run on both samples. CH<sub>4</sub>: full symbols, CO<sub>2</sub>: empty symbols. Conditions: temperature ramp in CH<sub>4</sub>:CO<sub>2</sub>:Ar = 68:31:1 mixture, 120 L h<sup>-1</sup> g<sub>cat</sub><sup>-1</sup>, at a 10 °C min<sup>-1</sup> rate to 600 °C and then isothermal 120 min hold time.

discerned at wavenumbers 3015 and 1304 cm<sup>-1</sup> and 2360 and 2340 cm<sup>-1</sup>, respectively. Comparing the unpromoted catalyst with its ZrO<sub>2</sub> support, we can conclude that bidentate formate species (2878, 1570, 1365 cm<sup>-1</sup>) dominate over bicarbonates<sup>51</sup> detected at 1627, 1419 and 1224 cm<sup>-1</sup> on its surface at 300 °C (Fig. 4a, curves A and B). This means that *via* finite dissociation of CH<sub>4</sub> on Ni particles H<sub>s</sub> is produced that accelerates the bicarbonate → formate transition. Chemisorbed CO on Ni is already detected at 2054 cm<sup>-1</sup>. Inspection of the spectrum at 500 °C taken on Ni/ZrO<sub>2</sub> (Fig. 4b, curve B) revealed that formate species may still be present at 1568 cm<sup>-1</sup> together with mono- and polydentate carbonates (1537 cm<sup>-1</sup>).

As for the sodium-promoted case, the difference under a DRM mixture between the support and the catalyst is not so clearly seen. On the Na-Ni/ZrO<sub>2</sub> catalyst, a few OH at 3696 cm<sup>-1</sup>, bidentate carbonates<sup>52</sup> at 1645 cm<sup>-1</sup>, bridged bidentate carbonate<sup>53</sup> at 1685 cm<sup>-1</sup>, monodentate carbonate at 1561 and 1350 cm<sup>-1</sup> plus CO chemisorbed on Ni (at 2036 cm<sup>-1</sup>) are observed at 300 °C. At 500 °C (see Fig. 4b), the situation is very similar except for the missing carbonyls on Ni and the absence of bands at 1680 and 1252 cm<sup>-1</sup> on Na-Ni/ZrO<sub>2</sub> but still having bands at 1630, 1555 and 1346 cm<sup>-1</sup> (bidentate and monodentate carbonate). Although gas phase CH<sub>4</sub> obscures the region, we claim that there is no sign of formates at any of the temperatures on Na-Ni/ZrO<sub>2</sub> under dry reforming mixture. Moreover, bridged bidentate and bidentate carbonates form only on Na-Ni/ZrO<sub>2</sub> due to the presence of sodium on the surface; the former seems to be destabilized (converted) on the Ni-containing catalyst.

### Catalytic properties and investigation of the spent samples by TEM and TPO

**DRM short tests and 24 h stability tests in the continuous flow fixed bed reactor.** Experiments in the tubular reactor were carried out with a CH<sub>4</sub>:CO<sub>2</sub>:Ar = 68:31:1 mixture at at-



**Fig. 6** TEM images taken after short term catalytic tests on (a) Ni/ZrO<sub>2</sub> and (b) Na-Ni/ZrO<sub>2</sub>. (c) HRTEM image of a single Ni particle at the end of a nanotube in the spent Na-Ni/ZrO<sub>2</sub>.

mospheric pressure in two ways: i) short tests after reduction at 600 °C in H<sub>2</sub> consisting of a temperature ramp in DRM

mixture to 600 °C followed by an isothermal hold for 2 hours, and ii) stability tests after a 700 °C reduction treatment at constant 675 °C reaction temperature.

Fig. 5 shows the results of the short test. Slightly higher CH<sub>4</sub> and lower CO<sub>2</sub> conversion could be achieved by the Ni/ZrO<sub>2</sub> catalyst at the end of the temperature ramp, and it was deactivated more at 600 °C than the promoted sample. The ratio of CO<sub>2</sub>/CH<sub>4</sub> conversion was about the same for both samples at the end of the experiment, but the H<sub>2</sub>/CO ratio was lower for Ni/ZrO<sub>2</sub> and it changed from 0.71 to 0.55, reflecting some deactivating tendency during the 2 hours of the isothermal part.<sup>54</sup> If the H<sub>2</sub>/CO ratio is lower than the theoretical, it is generally considered that besides DRM, reverse water gas shift happens<sup>55</sup> (note that water was not quantified during the measurements, but H<sub>2</sub>O *m/z* = 18 signal was fairly low and constant). However, if reverse WGSR would account for the lower H<sub>2</sub>/CO ratio, the CO<sub>2</sub> conversion should be higher on Ni/ZrO<sub>2</sub>. Clearly, this is not the case. We believe that this small difference in the H<sub>2</sub>/CO ratio is caused by the different reaction routes producing CO and H<sub>2</sub> on the two samples. Most probably the CO<sub>2</sub> dissociation into CO is favored on Ni/ZrO<sub>2</sub>, resulting in more CO.

TEM measurements on the spent catalysts are shown in Fig. 6a–c. Fig. 6a shows a 5 nm size Ni particle (indicated by an arrow) covered by graphitic layers and whirling carbon nanotubes or filaments located also on the support particles of Ni/ZrO<sub>2</sub>. The carbonaceous deposit on the Na–Ni/ZrO<sub>2</sub> sample is composed of disordered carbon nanotubes sometimes with Ni particles at their ends. We observed an amorphous layer or shell on the support particles (indicated by arrows in Fig. 6b) that could also be carbonaceous deposits. The HRTEM image in Fig. 6c shows a 22 nm Ni particle at the end of a carbon nanotube. In the light of the nanotube formation mechanism, the lattice period of 2.00–2.01 Å measured at the outer line or the border of a Ni particle may represent (113) Ni<sub>3</sub>C, the 2.05 Å might be a strained Ni (111) and the one with 2.08 Å spacing is assigned to NiO (200) lattice. The largest measured period of 2.36 Å fits neither Ni nor Ni carbide; however, it can be indexed as (011) of Ni(OH)<sub>2</sub> or (011) of NiOOH spacing. We can thus declare that NiO, probably Ni(OH)<sub>2</sub> and Ni/Ni<sub>3</sub>C, can be observed beside each other in small patches or domains of the metal surface. Indeed, we cannot prove if the oxidized forms of nickel were formed during the reaction or after the handling of the spent sample in air, but we suppose that some of them were already present during the reaction. If so, we tentatively suggest that the neighboring Ni species with different oxidation states keep the particle active, since these kinds of nanodomains – making a “ruffled” Ni look – were also seen on other metal particles of this sample, while none was observed on Ni/ZrO<sub>2</sub>.

Fig. 7 shows the results of TPO measurements after the short catalytic tests (together with those after long tests discussed later on). On Na–Ni/ZrO<sub>2</sub> 4.2 mg carbon/10 mg<sub>cat</sub> (42 wt% C) was found, while only 2.1 mg C/10 mg<sub>cat</sub> (21 wt% C) was found on the unpromoted sample, although the latter sample was less active at the end of the test. The different shape of the TPO curves and the descending part of the CO<sub>2</sub>

signal after the 600 °C temperature plateau reflects a difference in the kinetics of the coke oxidation process, being faster on Na–Ni/ZrO<sub>2</sub>. This means that although the amount of deposited coke is larger, it is not so strongly held and can be removed more easily. In contrast, the lesser amount of coke (half amount) on Ni/ZrO<sub>2</sub> depresses the catalytic activity of Ni sites to a larger extent (lower activity) and it was more difficult to remove. It is widely reported in the literature that Ni particle size or metal loading may increase the amount of coke sometimes without losing catalytic activity.<sup>22</sup> In our case, metal dispersion determined by CO pulse chemisorption was higher for the Ni/ZrO<sub>2</sub> sample; however, the number of Ni particles observed in the TEM images of the spent samples was not sufficient to determine the average particle size, and we know that reaction conditions might cause extra sintering of the metal. Still, keeping all these in mind, it seems that the similar size Ni particles co-operating with the Na oxide/carbonate promoter transfer a part of the surface coke far from the active Ni sites.

The results of the long term (24 h) catalytic runs are depicted in Fig. 8. In this case, significant differences were seen: Na–Ni/ZrO<sub>2</sub> was active and stable (concerning methane conversion) while the unpromoted catalyst practically died after the daylong reaction at 675 °C in excess methane. On Na–Ni/ZrO<sub>2</sub> both the CH<sub>4</sub> and the CO<sub>2</sub> conversion values at the end of the stability test were 70% of the corresponding starting values, meaning that the rates of Na–Ni/ZrO<sub>2</sub> deactivation in terms of CH<sub>4</sub> and CO<sub>2</sub> should be very similar. This suggests that the CH<sub>4</sub> and CO<sub>2</sub> activation routes are equally working and well balanced.

TEM measurements were used to explore the structure of the samples after the stability test as well. Fig. S5† shows that numerous long nanotubes were formed on Ni/ZrO<sub>2</sub> and some of them contained encapsulated Ni particles at the tips, while fewer carbon nanotube were found on Na–Ni/ZrO<sub>2</sub>. The deposited coke was oxidized again by TPO measurements (see Fig. 7).




Fig. 7 TPO curves of the spent samples obtained after the short and the long term (stability) tests. Short tests: full symbol, long test: empty symbol. CO<sub>2</sub> production was measured by QMS and temperature was ramped during TPO to 600 °C or 750 °C after the short or stability tests, respectively.




Fig. 8 Methane and CO<sub>2</sub> conversion curves during long term stability run on both samples. CH<sub>4</sub>: empty symbols, CO<sub>2</sub>: full symbols. Conditions: after reduction at 750 °C/0.5 h cooling to  $T = 675$  °C in He, then DRM with CH<sub>4</sub>:CO<sub>2</sub>:Ar = 68:31:1 mixture, 120 L h<sup>-1</sup> g<sub>cat</sub><sup>-1</sup>.


The unpromoted sample had a first TPO peak at around 530 °C and a second more definite one at 670 °C, summing all together, 3 mg C/10 mg<sub>cat</sub> (30 wt% C). The complete deactivation should be explained by the buried Ni particles and not by significant sintering, because  $d > 50$  nm particles (either ZrO<sub>2</sub> or Ni) were not observed by TEM. Again, it was more difficult to remove the surface coke from the unpromoted sample (high temperature TPO peak), suspecting a tough, graphitic structure and a less effective coke oxidation ability of the catalyst. The Na-promoted sample produced less (2.3 mg C/10 mg<sub>cat</sub> – 23 wt% C) carbon deposit now and even less than in the short term catalytic runs with a low 602 °C TPO peak maximum. We might estimate an average rate of coking for these isothermal experiments based on the 24 hour time: it is  $2.08 \times 10^{-4}$  and  $1.59 \times 10^{-4}$  g<sub>carbon</sub> g<sub>cat</sub><sup>-1</sup> min<sup>-1</sup> for Ni/ZrO<sub>2</sub> and Na-Ni/ZrO<sub>2</sub>, respectively. This shows again the positive effect of sodium promotion: the coke on the promoted catalyst is a very mobile and reactive type and does not cause significant deactivation. In the case of 5% Ni/Ce-Pr oxide catalysts, the introduction of 20 atom% Pr in the ceria lattice caused a significant reduction in the rate of inactive carbon formation with only a marginal decrease in the catalyst's activity and stability, but further increase of Pr loading caused a decrease in activity with drastic reduction of deposited carbon, which was explained partly by the inhibiting effect of inactive adsorbed carbonates as determined by SSITKA.<sup>24</sup> The sodium content in our case is significantly lower (Na/Zr = 0.03); however, a decrease in coking rate is observed already. (When the same sodium promotion was done on our 1% Ni/ZrO<sub>2</sub> catalyst,<sup>35</sup> coke formation was further decreased with the concomitant decrease of activity as in the case of the above literature reference. Based on this apparent parallel, we might suspect that on that 1% Ni/ZrO<sub>2</sub> sample some inactive carbonate species play a role. However, this is not the topic of the present work.)

**Catalytic investigations at sub-atmospheric pressure in a closed loop circulation reactor using <sup>13</sup>CO<sub>2</sub>.** Our closed loop

circulation system (shown in Fig. S1†) working at sub-atmospheric pressure allows us to follow the interconversion of carbon atoms of both reactants because one of the reactants is labeled (<sup>13</sup>CO<sub>2</sub>). Temperature programmed DRM reactions in this case were conducted with a stoichiometric ratio of the reactants (~25 mbar CH<sub>4</sub> + ~25 mbar labeled <sup>13</sup>CO<sub>2</sub>) (CH<sub>4</sub> reactant contained 2% Ar for internal reference of mass signal changes due to the pressure and temperature increase during the experiment). The dry reforming reactions were always preceded by a reduction at 600 °C in atmospheric H<sub>2</sub> flow and evacuation.

First, the results of the ramp-hold experiments are discussed (a temperature ramp from about 100 °C up to 600 °C followed by a 30 min isothermal hold, evacuation of the gas phase, then cooling). In Fig. 9, on the left Y axis the intensity of the chosen mass numbers corresponding to the gas phase components *versus* time are shown (on the X axis 1 MS cycle equals 26 s), and on the right Y axis the reaction temperature *versus* time (=MS cycles) can be followed. Although quantitative analysis (exact concentrations) cannot be obtained here due to the significant pressure increase during reaction, comparison of the experimental curves normalized to the Ar signal ( $m/z = 40$ ) can still provide qualitative information about the catalysts. As the reaction starts at about 300 °C, the products such as <sup>13</sup>CO ( $m/z = 29$ ), then <sup>12</sup>CO ( $m/z = 28$ ) and H<sub>2</sub> ( $m/z = 2$ ), can be observed with the concomitant decrease of the mass signal of reactants <sup>12</sup>CH<sub>4</sub> ( $m/z = 15$ ) and <sup>13</sup>CO<sub>2</sub> ( $m/z = 45$ ). It is easy to see (compare Fig. 9a and b) that Ni/ZrO<sub>2</sub> is more active since it converts most of the reactants as the temperature reaches 600 °C, while on Na-Ni/ZrO<sub>2</sub> to get the same conversion, longer reaction time is needed; in particular, the CH<sub>4</sub> conversion is retarded. During the isothermal part of the experiment (600 °C for 30 min) the transformation of reactants, particularly that of <sup>12</sup>CH<sub>4</sub>, continues on Na-Ni/ZrO<sub>2</sub>, showing that the system is not at equilibrium; accordingly, <sup>12</sup>CO and H<sub>2</sub> formation proceeds (designated by arrows), but oxygen providing CO<sub>2</sub> molecules are no more present in the gas phase. This suggests that a pool of active oxidants is still available on the surface.

If we take a closer look at the low concentration components formed at the ascending part of the temperature ramp shown in Fig. 9c and d, first <sup>13</sup>CO originating from carbon dioxide reactant can be observed on both samples. Then, <sup>12</sup>CO coming from methane can be detected, but on Ni/ZrO<sub>2</sub> <sup>12</sup>CO appears at the same time/temperature like <sup>12</sup>CO<sub>2</sub> and H<sub>2</sub>, while in the case of Na-Ni/ZrO<sub>2</sub> the <sup>12</sup>CO<sub>2</sub> and H<sub>2</sub> formation precedes by 30 °C the <sup>12</sup>CO appearance. This suggests that at the onset of methane dissociation (indicated by the sharp increase of H<sub>2</sub> signal intensity), the available oxygen species are in excess and can make possible total oxidation of <sup>12</sup>C on the promoted sample. The <sup>12</sup>CO<sub>2</sub> formation has a local maximum at about 530 °C and 560 °C for Ni/ZrO<sub>2</sub> and Na-Ni/ZrO<sub>2</sub>, respectively. Afterwards, the unlabeled <sup>12</sup>CO<sub>2</sub> together with the labeled <sup>13</sup>CO<sub>2</sub> is consumed in dry reforming as the temperature increases. Johnson and Shamsi<sup>56</sup> observed during <sup>13</sup>CH<sub>4</sub> labeled flow dry reforming experiments the formation of <sup>13</sup>CO<sub>2</sub> at 800 °C.




**Fig. 9** Ramp-hold type dry reforming reaction with a  $^{13}\text{CO}_2$ : $^{12}\text{CH}_4 = 1$  mixture in the closed loop circulation system on (a) Ni/ZrO<sub>2</sub> and (b) Na-Ni/ZrO<sub>2</sub>. (c) Enlargement of low intensity signals of spectrum “a” and (d) enlargement of low intensity signals of spectrum “b”. Conditions: ~25 mbar each reactant ( $^{12}\text{CH}_4$  contains 2% Ar), temperature ramp with 10 °C min<sup>-1</sup> up to 600 °C then isothermal 30 min at 600 °C. 1 MS cycle = 26 s.

Eye-catching is the evolution of labeled  $^{13}\text{CH}_4$  ( $m/z = 17$ ) which already happens on Ni/ZrO<sub>2</sub> at 490 °C. This  $^{13}\text{CH}_4$  is formed by surface hydrogenation of the  $^{13}\text{CO}_2$ / $^{13}\text{CO}$  source. On Ni/ZrO<sub>2</sub> the FTIR measurements proved the effective hydrogenation of carbonates leading to formates under dry reforming, that takes place probably at the Ni-ZrO<sub>2</sub> interface or by H spill-over to further support sites. This hydrogenation route produces methane in the appropriate temperature and concentration window from  $\text{H}^{13}\text{COO}_s$ / $^{13}\text{CHO}_s$ / $^{13}\text{C}_s$ . We should keep in mind that the surface of Ni was found fully metallic by XPS, and Ni metal is a requirement of methanation activity. Furthermore, methanation is a structure sensitive reaction and is sensitive to the presence of H<sub>2</sub> that induces CO dissociation.<sup>57</sup> However, dissociation of CO is inhibited by O traces.<sup>58</sup>

In the case of the promoted catalyst (Fig. 9d), the  $^{13}\text{CH}_4$  formation is retarded until the shortage of oxygen/oxidants (from CO<sub>2</sub>), although abundant H<sub>2</sub> is available. Arena *et al.*<sup>39</sup> reported that surface diffusion of hydrogen is hindered by alkali patches on Ni. This might also be valid for the present case, further suppressing the methanation route. Although we could not go higher than 500 °C during DRIFT measurements, we suppose that some short-lived carbonates are present even at 600 °C due to the Na<sub>2</sub>O promoter around Ni/Ni(OH)<sub>2</sub>, and by continuous formation and decomposition they provide oxygen to  $^{12}\text{C}_x\text{H}_y$  or C<sub>s</sub> removal. Indeed, the HRTEM image in Fig. S6† shows a Ni particle with a shell of Ni(OH)<sub>2</sub> and NiOOH patches of the Na-Ni/ZrO<sub>2</sub> sample detected after this ramp-hold experiment. TPO measurement after these ramp-hold reactions revealed different types and amounts of deposited coke as depicted in Fig. 10a. For a clearer view, the integral signal of CO<sub>2</sub> formation obtained in the closed loop circulation system was differentiated. On Ni/ZrO<sub>2</sub>, surface carbon originating from the  $^{12}\text{CH}_4$  source was oxidized at 330 °C with a significant tail at 520 °C. At the higher temperature range  $^{13}\text{CO}_2$  was also detected, meaning that the less reactive carbon deposit was a mixed type (from both  $^{12}\text{C}$  and  $^{13}\text{C}$ ). This means that methane leaves an easily oxidizable (low temperature TPO peak) carbon and a more resistant type of carbon (high temperature tail) on Ni/ZrO<sub>2</sub>; moreover, a “mixed type” coke product, partly from gas phase  $^{12}\text{CO}$  and  $^{13}\text{CO}$ , is also formed. In contrast, on Na-Ni/ZrO<sub>2</sub> only  $^{12}\text{C}$  remained with a wide reactivity/distribution. The detailed quantification of the  $^{12}\text{C}$  and  $^{13}\text{C}$  ratio of the total deposited carbon on both catalysts and under both types of reactions is collected in Table 2. This analysis helps to distinguish the contribution of the CO<sub>2</sub> activation route to the inactive carbon formation for each catalyst and condition as was done in ref. 23–25. It is seen in Table 2 that the amount of deposited carbon was drastically decreased upon sodium promotion, while the contribution of CO<sub>2</sub> to the total carbon is similarly low (only 10% on Ni/ZrO<sub>2</sub>, and zero on the promoted catalyst) in the ramp-hold experiments.

The other dry reforming experiments carried out in the circulation system were of isothermal type (600 °C reaction for 30 min, then evacuation of the gas phase, and cooling). These results are shown in detail in Fig. S7a–d.† By the end



**Fig. 10** TPO experiments in the circulation system after labeled DRM reaction carried out *via* the (a) ramp-hold manner and (b) isothermal manner at 600 °C.  $^{12}\text{CO}_2$ : full symbols,  $^{13}\text{CO}_2$ : empty symbols. The original measured integral signals are differentiated to get peak-shaped curves.

of 30 min, practically all the reactants were converted, but on Ni/ZrO<sub>2</sub> at a significantly higher rate. The low concentration components right after the start of the reaction showed exactly the same profile as before:  $^{12}\text{CO}_2$  immediately formed and then was consumed (but faster on Ni/ZrO<sub>2</sub>), while  $^{13}\text{CH}_4$  was detected within 1 or after 4.5 min on Ni/ZrO<sub>2</sub> and Na-Ni/ZrO<sub>2</sub>, respectively. The tendentious decrease of both CO products and the increase of CO<sub>2</sub> signals on Ni/ZrO<sub>2</sub> suggest that CO disproportionation happened at 600 °C leaving some C<sub>s</sub> on Ni. In contrast, methane conversion was relatively slow on Na-Ni/ZrO<sub>2</sub>, and based on the less amount of H<sub>2</sub> evolved

compared to that on Ni/ZrO<sub>2</sub>, we assume that H<sub>s</sub>/OH<sub>s</sub> species remained on the catalyst.

The corresponding derived TPO curves of Ni/ZrO<sub>2</sub> (Fig. 10b) show that  $^{12}\text{CO}_2$  was formed again in 2 ranges, below and above 400 °C, and both peaks contained 2 overlapped components (paired at 280–330 °C and at 490–550 °C).  $^{13}\text{CO}_2$  appeared only above 350 °C. The amount of surface carbon removable at low temperature and formed only from methane on Ni/ZrO<sub>2</sub> was less now, but the high temperature CO<sub>2</sub> peak was larger than that after the ramp-hold run. However, in total, about the same amount of coke formed as in the ramp-hold experiment but the CO<sub>2</sub> contribution increased now to about 38.6% (Table 2). Generally, the temperature of the TPO peaks is influenced by the structure, location and oxidation kinetics of coke. The low temperature peaks come from the easily oxidizable and probably CH<sub>x</sub> or amorphous carbon or carbide species; the high temperature ones must be deeply dehydrogenated, graphitic, and located either on Ni or on ZrO<sub>2</sub> support. We propose that the high temperature peaks on Ni/ZrO<sub>2</sub> were formed from the CO products *via* the Boudouard reaction ( $2\text{CO} \rightleftharpoons \text{C} + \text{CO}_2$ ) and from  $^{12}\text{CH}_4$  at the start of the reaction. The active sites for CO dissociation on this sample seem to be more effective/available during the isothermal experiment than during the ramp-hold type one because they might be less covered by carbon deposits originating solely from CH<sub>4</sub> decomposition (see the area of the low temperature peak). This again justifies the general view that at higher temperature less carbon deposit is expected to form.

In the case of the Na-Ni/ZrO<sub>2</sub> catalyst we observe now the presence of carbon from the  $^{13}\text{CO}_2$  reactant which was not the case during the ramp-hold type experiments: the even more negligible surface carbon was a “mixed type” with 45% contribution of  $^{13}\text{C}$ . This deposited carbon is assumed to either originate from CO products or may show that the CH<sub>4</sub> and CO<sub>2</sub> activation routes produce surface carbon with the same structural characteristics.

In general, we can observe that the contribution of  $^{13}\text{CO}_2$  in the deposited coke is increased during the isothermal experiments for both samples, when the reaction starts/proceeds faster. In contrast, on Ni/Ce-Pr oxides at higher reaction temperature (higher rate) the contribution of methane was increased.<sup>24</sup> We can hardly compare the two cases because in our isothermal experiments in this circulation system – especially on Ni/ZrO<sub>2</sub> – the conversion rate of reactants is too fast and the CO products in the gas phase over the catalyst may also contribute to the deposited coke *via* the Boudouard reaction. Note the main

**Table 2** Quantified results of TPO experiments in the circulation system after labeled DRM reactions carried out *via* the ramp-hold or the isothermal manner at 600 °C

Sample	T/°C and type of exp.	$^{12}\text{CO}_2/\mu\text{mol g}^{-1}$	$^{13}\text{CO}_2/\mu\text{mol g}^{-1}$	$^{12}\text{C}/^{13}\text{C}$	Total carbon/ $\mu\text{mol g}^{-1}$
Ni/ZrO <sub>2</sub>	600, ramp and hold	1425.9	159.2	8.95 (10) <sup>a</sup>	1585.1 (1.92) <sup>b</sup>
	600, isothermal	1030.8	647.6	1.59 (38.6) <sup>a</sup>	1678.3 (2.08) <sup>b</sup>
Na-Ni/ZrO <sub>2</sub>	600, ramp and hold	250.0	0.0	n/a (0) <sup>a</sup>	250.0 (0.3) <sup>b</sup>
	600, isothermal	46.3	38.0	1.22 (45.1) <sup>a</sup>	84.4 (0.11) <sup>b</sup>



<sup>a</sup> % contribution of the CO<sub>2</sub> activation route to the total surface carbon derived from both CH<sub>4</sub> and CO<sub>2</sub> activation routes. <sup>b</sup> Wt% carbon.

1 difference: coke did not form on the promoted sample solely  
 2 from CH<sub>4</sub> reactant as opposed to Ni/ZrO<sub>2</sub> under the same type  
 3 of isothermal reaction. This means that localized Na promotion  
 4 helps the gasification of a reactive surface carbon – probably  
 5 CH<sub>x</sub> type – in a continuous and effective way *via* the embedded  
 Na<sub>2</sub>O entities forming carbonates and acting according to the  
 reverse Boudouard reaction: CH<sub>x</sub> + CO<sub>2</sub> = 2CO + xH<sub>2</sub>.

### 10 The role of sodium promotion in the reaction mechanism and coke removal

11 Connecting the catalytic properties with all the structural re-  
 12 sults, we can draw the following statements. The highly hy-  
 13 drated Ni/ZrO<sub>2</sub> catalysts active in formate production under low  
 14 temperature dry reforming conditions will develop deactivating  
 15 type coke. Formate formation stems from the metal surface pro-  
 16 viding H<sub>2</sub>; thus part of that formate must be in the surrounding  
 17 of Ni particles occupying/poisoning the adsorption area from  
 18 the CO<sub>2</sub> reactant that could provide new active oxygen species  
 19 to C<sub>s</sub> removal. At high temperature, when the interface of Ni  
 20 might not play a significant role in CO<sub>2</sub> activation, but the  
 metal surface itself, CO disproportionation must be avoided in  
 order to obtain stable catalytic performance.

21 On Na–Ni/ZrO<sub>2</sub> formate was not observed; due to its com-  
 22 plete absence or its immediate decomposition to carbonates  
 23 the dry reforming ability was preserved without significant  
 24 deactivation. In this case the localized Na<sub>2</sub>O promotion on  
 25 and around the Ni/Ni(OH)<sub>2</sub> entities is of key importance.  
 26 Even though the existence of a bridged CO species at 1820  
 27 cm<sup>-1</sup> suggests a decreased C–O bond strength detected on  
 28 Na–Ni/ZrO<sub>2</sub>, increased CO dissociation ability was not  
 29 deducted here. The stable activity under our really demand-  
 30 ing dry reforming conditions is explained by the continuously  
 31 renewing oxygen pool from the balanced interconversion of  
 32 NaHCO<sub>3</sub>/Na<sub>2</sub>CO<sub>3</sub>/Na<sub>2</sub>O at the Ni–ZrO<sub>2</sub> interface or partially on  
 33 the surface of Ni particles. Ni – through dissociation of CH<sub>4</sub> –  
 34 provides H<sub>2</sub> to the decomposition of Na<sub>2</sub>CO<sub>3</sub> or NaHCO<sub>3</sub> to  
 35 CO<sub>2</sub> + O<sup>2-</sup> + Na<sup>+</sup> + H<sub>2</sub>O. During the process NiO<sub>x</sub>H<sub>y</sub> forms that  
 36 is reduced by C<sub>s</sub> or C<sub>x</sub>H<sub>y</sub> (from methane) back to Ni (and CO  
 37 and H<sub>2</sub>O forms). Then Na<sub>2</sub>O and the available CO<sub>2</sub> result in  
 38 Na<sub>2</sub>CO<sub>3</sub> again. These tentatively suggested reactions take  
 39 place simultaneously on small domains of the Ni surface or  
 40 at the interface. Some metallic Ni is required for CH<sub>4</sub>  
 41 dissociation, Ni(OH)<sub>2</sub> or NiOOH (NiO<sub>x</sub>H<sub>y</sub>) for carbon oxida-  
 42 tion. Our assumption is strongly supported by ref. 40, 41 and  
 43 59 reporting about the high CO<sub>2</sub> absorption capacity of bulk  
 44 Na<sub>2</sub>ZrO<sub>3</sub> in the presence of CO<sub>2</sub> at temperatures above 500  
 45 °C, resulting in a Na<sub>2</sub>CO<sub>3</sub> shell and a ZrO<sub>2</sub> layer beneath close  
 46 to the surface of bulk alkali zirconate as:



49 At higher temperature (~800–850 °C) or at lower CO<sub>2</sub> partial  
 50 pressure the Na<sub>2</sub>ZrO<sub>3</sub> is regenerated by CO<sub>2</sub> liberation, forming

51 Na<sub>2</sub>O that can react with ZrO<sub>2</sub> and producing Na<sub>2</sub>ZrO<sub>3</sub> again  
 52 (the reverse directions of reactions (3) and (4)).<sup>40,41,59</sup> We pro-  
 53 pose that the upwards diffusion of sodium ions in the surface  
 54 labile oxide lattice to capture CO<sub>2</sub> could result in some O<sup>2-</sup> spe-  
 55 cies being used up by C<sub>s</sub>. This must have multiple relevance at  
 high reaction temperatures of our long term catalytic tests. Un-  
 til there is a small amount of gas phase CO<sub>2</sub>, the “primary” car-  
 bon of methane reactant is removed and not deposited as coke  
 or hydrogenated back to CH<sub>4</sub>.

Concerning all the results, carbonates on Na–Ni/ZrO<sub>2</sub> are  
 suggested to take part in the reaction while on Ni/ZrO<sub>2</sub> the  
 formates must be only spectators in the course of dry  
 reforming.

## 15 Conclusions

16 In the present work, 0.6% Na–3% Ni/ZrO<sub>2</sub> catalyst was com-  
 17 pared to the reference 3% Ni/ZrO<sub>2</sub> sample. The localized Na  
 18 incorporation provided high basicity to the catalyst and  
 19 resulted in a NiO<sub>x</sub>H<sub>y</sub> that is in strong interaction with the  
 20 support compared to the reference. Na was enriched on the  
 21 surface and the inclusion of some sodium oxide into the  
 22 nickel (oxide) phase was suggested to happen and/or the Ni  
 23 surface became covered by Na<sub>2</sub>O or Na<sub>2</sub>CO<sub>3</sub> patches based on  
 24 XPS results and the decrease in CO chemisorption values. CO  
 25 TPD results suggested WGS activity on Na–Ni/ZrO<sub>2</sub> in con-  
 26 trast to Ni/ZrO<sub>2</sub>. DRIFTS measurement under flow of the dry  
 27 reforming mixture revealed the presence of bidentate formate  
 28 species on Ni/ZrO<sub>2</sub>, while no sign of formates was discerned  
 29 on Na–Ni/ZrO<sub>2</sub>. Apparently, CO<sub>2</sub> adsorption and activation  
 30 processes differ: bidentate carbonate is stabilized by basic ox-  
 31 ygen atoms influenced by sodium on Na–Ni/ZrO<sub>2</sub> while effec-  
 32 tive hydrogenation by Ni converts bicarbonates to formate  
 33 species on Ni/ZrO<sub>2</sub>.

34 The continuous flow catalytic tests in excess methane re-  
 35 vealed coke deposition on both samples, but the activity and  
 36 stability of Na–Ni/ZrO<sub>2</sub> was significantly higher. TPO experi-  
 37 ments proved that the surface carbon on the promoted cata-  
 38 lyst is a mobile and reactive type one and does not cause sig-  
 39 nificant deactivation.

40 In <sup>13</sup>CO<sub>2</sub> labeled stoichiometric DRM experiments in a  
 41 closed loop circulation system at sub-atmospheric pressure,  
 42 evolution of labeled <sup>13</sup>CH<sub>4</sub> was detected on Ni/ZrO<sub>2</sub> from the  
 43 <sup>13</sup>CO<sub>2</sub>/<sup>13</sup>CO/<sup>13</sup>C source, possibly due to the effective hydroge-  
 44 nation of carbonates at the Ni–ZrO<sub>2</sub> interface and the dissoci-  
 45 ation of <sup>13</sup>CO on Ni. In the case of the promoted catalyst, this  
 46 methanation (transfer of <sup>13</sup>C of <sup>13</sup>CO<sub>2</sub> to <sup>13</sup>CH<sub>4</sub>) is retarded  
 47 until the significant shortage of oxygen/oxidants, although  
 48 abundant H<sub>2</sub> is available. During DRM at constant 600 °C,  
 49 CO disproportionation happened on Ni/ZrO<sub>2</sub> leaving some  
 50 carbon on Ni, besides the coke formed solely from the CH<sub>4</sub>  
 51 source. In contrast, carbonaceous deposit did not form on  
 52 Na–Ni/ZrO<sub>2</sub> solely from the CH<sub>4</sub> reactant, only from CO prod-  
 53 ucts and moreover in an insignificant amount. We suppose  
 54 that some short-lived carbonates/hydrocarbonates are present  
 55 even at high temperatures in contact with the ZrO<sub>2</sub>-

1 embedded  $\text{Na}_2\text{O}$  and  $\text{Ni}/\text{Ni}(\text{OH})_2$  surface, continuously  
forming and decomposing, thus oxidizing the  $^{12}\text{C}_x\text{H}_y$  or  $\text{C}_s$   
5 surface species to  $^{12}\text{CO}$ . This is supported by literature analogies  
dealing with the high temperature reversible  $\text{CO}_2$  capture  
of bulk  $\text{Na}_2\text{ZrO}_3$ . The tentatively suggested reactions take  
place simultaneously on small domains of Ni or at the inter-  
face. Concerning all the results, carbonates on  $\text{Na-Ni}/\text{ZrO}_2$   
10 are suggested to take part in the reaction while on  $\text{Ni}/\text{ZrO}_2$   
the formates are only spectators in the course of low temper-  
ature dry reforming. SSITKA experiments are under progress  
to ascertain this statement.

The ease of sample preparation and the good properties of  
the resulting  $\text{Na}_2\text{O}$ -modified catalyst deserve attention and  
may propagate further research on carbon resistance of Ni  
15 supported on non-reducible  $\text{ZrO}_2$ .

## Conflicts of interest

Q8

## Acknowledgements

The authors are indebted to Era-Chemistry and the Hungar-  
ian National Research Fund (OTKA NN#107170) for financial  
support. Professor Johannes Lercher's group at the Technical  
University of Munich, Department of Chemistry is acknowl-  
25 edged for providing us with the  $\text{ZrO}_2$  support.

## References

- 1 P. M. Mortensen and I. Dybkjaer, *Appl. Catal., A*, 2015, **495**, 141.
- 2 M. K. Nikoo and N. A. S. Amin, *Fuel Process. Technol.*, 2011, **92**, 678.
- 3 A. Yamaguchi and E. Iglesia, *J. Catal.*, 2010, **274**, 52.
- 4 J. Wei and E. Iglesia, *J. Catal.*, 2004, **224**, 370.
- 5 N. Sun, X. Wen, F. Wang, W. Peng, N. Zhao, F. Xiao, W. Wei, Y. Sun and J. Kang, *Appl. Surf. Sci.*, 2011, **257**, 9169.
- 6 B. B. Baeza, C. M. Pedrero, M. A. Soria, A. G. Ruiz, U. Rodemerck and I. R. Ramos, *Appl. Catal., B*, 2013, **129**, 450.
- 7 S. Sokolov, E. V. Kondratenko, M. M. Pohl and U. Rodemerck, *Int. J. Hydrogen Energy*, 2013, **38**, 16121.
- 8 S. Damyanova, B. Pawelec, K. Arishtirova, M. V. M. Huerta and J. L. G. Fierro, *Appl. Catal., B*, 2009, **89**, 149.
- 9 A. S. Bobin, V. A. Sadykov, V. A. Rogov, N. V. Mezentseva, G. M. Alikina, E. M. Sadvovskaya, T. S. Glazneva, N. N. Sazonova, M. Y. Smirnova, S. A. Veniaminov, C. Mirodatos, V. Galvitta and G. B. Martin, *Top. Catal.*, 2013, **56**, 958.
- 10 L. M. Aparicio, *J. Catal.*, 1997, **165**, 262.
- 11 M. C. J. Bradford and M. A. Vannice, *J. Catal.*, 1998, **173**, 157.
- 12 Y. Z. Chen, B. J. Liaw and W. H. Lai, *Appl. Catal., A*, 2002, **230**, 73.
- 13 M. A. Goula, A. Lemonidou and A. M. Efstathiou, *J. Catal.*, 1996, **161**, 626.
- 14 J.-M. Wei, B.-Q. Xu, J.-L. Li, Z.-X. Cheng and Q.-M. Zhu, *Appl. Catal., A*, 2000, **196**, 167.
- 15 Y. Kathiraser, U. Oemar, E. T. Saw, Z. Li and S. Kawi, *Chem. Eng. J.*, 2015, **278**, 62.
- 16 C. Papadopoulou, H. Matralis and X. Verykios, in *Catalysis for Alternative Energy Generation*, ed. L. Guzzi and A. Erdöhelyi, Springer Science+Business Media New York, 2012, pp. 57–128.
- 17 M.-S. Fan, A. Z. Abdullah and S. Bhatia, *ChemCatChem*, 2009, **1**, 192.
- 18 J. W. Han, C. Kim, J. S. Park and H. Lee, *ChemSusChem*, 2014, **7**, 451.
- 19 A. Horváth, G. Stefler, O. Geszti, A. Kienneman, A. Pietraszek and L. Guzzi, *Catal. Today*, 2011, **169**, 102.
- 20 E. Lovell, Y. Jiang, J. Scott, F. Wang, Y. Suhardja, M. Chen, J. Huang and R. Amal, *Appl. Catal., A*, 2014, **473**, 51.
- 21 L. F. Li, C. Xia, C. T. Au and B. S. Liu, *Int. J. Hydrogen Energy*, 2014, **39**, 10927.
- 22 C. Gennequin, M. Safariamin, S. Siffert, A. Aboukaïs and E. Abi-Aad, *Catal. Today*, 2011, **176**, 139.
- 23 M. M. Makri, M. A. Vasiliades, K. C. Petallidou and A. M. Efstathiou, *Catal. Today*, 2015, **259**, 150.
- 24 M. A. Vasiliades, M. M. Makri, P. Djinić, B. Erjavec, A. Pintar and A. M. Efstathiou, *Appl. Catal., B*, 2016, **197**, 168.
- 25 M. A. Vasiliades, P. Djinić, L. F. Davlyatova, A. Pintar and A. M. Efstathiou, *Catal. Today*, 2017, DOI: 10.1016/j.cattod.2017.03.057.
- 26 A. Horváth, L. Guzzi, A. Kocsonya, G. Sáfrán, V. La Parola, L. F. Liotta, G. Pantaleo and A. M. Venezia, *Appl. Catal., A*, 2013, **468**, 250.
- 27 L. Guzzi, G. Stefler, O. Geszti, I. Sajó, Z. Pászti, A. Tompos and Z. Schay, *Appl. Catal., A*, 2010, **375**, 236.
- 28 A. Ballarini, F. Basile, P. Benito, I. Bersani, G. Fornasari, S. de Miguel, S. C. P. Maina, J. Vilella, A. Vaccari and O. A. Scelza, *Appl. Catal., A*, 2012, **433–434**, 1.
- 29 A. D. Ballarini, S. R. de Miguel, E. L. Jablonski, O. A. Scelza and A. A. Castro, *Catal. Today*, 2005, **107–108**, 481.
- 30 M. W. Balakos and S. S. C. Chuang, *J. Catal.*, 1992, **138**, 733.
- 31 R. D. Gonzalez and H. Miura, *J. Catal.*, 1982, **77**, 338.
- 32 C. Zhang, Y. Li, Y. Wang and H. He, *Environ. Sci. Technol.*, 2014, **48**, 5816.
- 33 T. Horiuchi, K. Sakuma, T. Fukui, Y. Kubo, T. Osaki and T. Mori, *Appl. Catal., A*, 1996, **144**, 111.
- 34 T. Osaki and T. Mori, *J. Catal.*, 2001, **204**, 89.
- 35 M. Németh, Z. Schay, D. Srankó, J. Károlyi, G. Sáfrán, I. Sajó and A. Horváth, *Appl. Catal., A*, 2015, **504**, 608.
- 36 A. Packter and S. C. Uppaladinni, *Krist. Tech.*, 1975, **10**, 985.
- 37 Q. J. Chen, J. Zhang, Q. W. Jin, B. R. Pan, W. B. Kong, T. J. Zhao and Y. H. Sun, *Catal. Today*, 2013, **215**, 251.
- 38 F. Arena, A. L. Chuvilin and A. Parmaliana, *J. Phys. Chem.*, 1995, **99**, 990.
- 39 F. Arena, F. Frusteri and A. Parmaliana, *Appl. Catal., A*, 1999, **187**, 127.
- 40 H. G. Jo, H. J. Joon, C. H. Lee and K. B. Lee, *Ind. Eng. Chem. Res.*, 2016, **55**, 3833.
- 41 G. G. Santillán-Reyes and H. Pfeiffer, *Int. J. Greenhouse Gas Control*, 2011, **5**, 1624.

- 1 42 A. F. Carley, S. D. Jackson, J. N. O'Shea and M. W. Roberts, *Surf. Sci.*, 1999, **440**, 868.
- 43 T. Shido and Y. Iwasawa, *J. Catal.*, 1993, **141**, 71.
- 5 44 A. Kitla, O. V. Safonova and K. Föttinger, *Catal. Lett.*, 2013, **143**, 517.
- 45 P. Panagiotopoulou and D. I. Kondarides, *J. Catal.*, 2008, **260**, 141.
- 46 L. F. Liotta, G. A. Martin and G. Deganello, *J. Catal.*, 1996, **164**, 322.
- 10 47 K. I. Hadjiivanov and G. N. Vayssilov, *Adv. Catal.*, 2002, **47**, 307.
- 48 J. M. Pigos, C. J. Brooks, G. Jacobs and B. H. Davis, *Appl. Catal., A*, 2007, **319**, 47.
- 49 E.-M. Kock, M. Kogler, T. Bielz, B. Klotzer and S. Penner, *J. Phys. Chem. C*, 2013, **117**, 17666.
- 15 50 J. H. Bitter, *PhD thesis*, University of Twente, Enschede, The Netherlands, 1997.
- 51 S. E. Collins, M. A. Baltanás and A. L. Bonivardi, *J. Phys. Chem. B*, 2006, **110**, 5498.
- 52 D. Heyl, U. Rodemerck and U. Bentrup, *ACS Catal.*, 2016, **6**, 6275.
- 53 R. W. Stevens, R. V. Siriwardane and J. Logan, *Energy Fuels*, 2008, **22**, 3070.
- 54 G. K. Reddy, S. Loridant, A. Takahashi, P. Delichère and B. M. Reddy, *Appl. Catal., A*, 2010, **389**, 92.
- 55 S. Haag, M. Burgard and B. Ernst, *J. Catal.*, 2007, **252**, 190.
- 56 A. Shamsi and C. D. Johnson, *Catal. Today*, 2003, **84**, 17.
- 10 57 M. P. Andersson, F. Abild-Pedersen, I. N. Remediakis, T. Bligaard, G. Jones, J. Engbæk, O. Lytken, S. Horch, J. H. Nielsen, J. Sehested, J. R. Rostrup-Nielsen, J. K. Nørskov and I. Chorkendorff, *J. Catal.*, 2008, **255**, 6.
- 58 S. Fujita, M. Nakamura, T. Doi and N. Takezawa, *Appl. Catal., A*, 1993, **104**, 87.
- 59 S. Wang, C. An and Q.-H. Zhang, *J. Mater. Chem. A*, 2013, **1**, 3540.

20

20

25

25

30

30

35

35

40

40

45

45

50

50

55

55